

EXHIBIT A

Lacey City Hall - Office 1063 Remodel

Scope of work: Make Office 1063 bigger by removing two walls and then frame straight across + eliminate the "bump-out" that currently exists in office 1063 - see before & after drawings.

- Protection tent work area
- Demo two walls, carpet, tile + base
- Cap floor drain in Storage Rm. 1064
- Remove partial ceiling grid (store tile)
- Frame new wall to structure above
- Frame window soffit
- Minor electrical, relocate ceiling troffer
- Hang sheetrock, tape + coat
- Prime + paint (both rooms)
- Restore ceiling grid (both rooms)
- Install carpet tiles, rubber base
- Install ceramic tile base (from demo)

